



**NOTES**

1. USE 3 SACK LEAN CEMENT SLURRY MIX BACKFILL
2. ALLOW SLURRY TO SET 12 HOURS BEFORE PLACING ASPHALT CONCRETE IN TRENCH
3. SAND REQUIREMENT MAY BE WAIVED IN SOFT SOIL AT THE CITY ENGINEER'S DISCRETION
4. PAVING TO FOLLOW WITHIN A MAXIMUM OF 24 HOURS FROM EXCAVATING

All units are in metric  
 Non-metric units in brackets  
 ACAD FILENAME: TELCO

**CITY OF MENLO PARK STANDARD DETAILS**



NO.	REVISIONS	DATE

**TELCO ROCKWHEEL TRENCH**

APPROVED

*John A. Arman*  
 Director of Engineering Services R.C.E. No. 40998

DRAWN	CHECKED	DATE	SCALE	SHEET
		1-1-97	NTS	

STD. DETAIL No.: **ST-10**